STOCKPILE REMOVAL AND DISPOSAL

Description: This work shall consist of the screening, segregating and loading of approximately 700,000 cubic yards of natural lime stone, dirt, silt, and pea gravel, for use by contractors on offsite projects. Removal of the existing stockpile shall be made to the point where all the aggregates/soil above grade has been removed to street grade level.

The location of the existing stockpile is on Metropolitan Water Reclamation District of Greater Chicago (MWRDGC) property east of Cicero Avenue on north side of Cal Sag Road in the Village of Crestwood, IL.

CONSTRUCTION REQUIREMENTS

General: Prior to beginning operations in the area, Contractor shall notify the Village of Crestwood who currently has a 2 year permit for the use of this site from the MWRDGC, in order to obtain access to this property. All Village requirements and Metropolitan Water Reclamation District of Greater Chicago requirement shall be met before access is granted. Notification shall be made one week in advance to starting work. The Contractor shall be responsible for reviewing the Permit and adhering to the conditions of the permit prior to the commencement of work, including but not limited to insurance requirements.

The Contractor's sequence of operations shall be in such a way to limit excessive dirt and debris and minimize traffic congestions on the roadways.

Site Operation Plan: The Contractor shall develop a project specific site plan and submit the plan to the Village Engineer a minimum of two weeks before beginning the removal activities. The plan shall outline the procedures, subcontractors if any, construction timelines, and the final project site where this material is being used. The plan shall also meet all the federal, State and local requirements for the screening, segregating and loading of this spoil material. Any debris screened from these piles, shall be removed and disposed of in accordance with State, Federal and Local regulations.

Stockpile removal and disposal shall be performed only when temperature in the shade is at least 40º F (5º C) and the forecast calls for no rain.

Method of Measurement: This work shall be measured for payment in TON as measured at the project site.

Basis of Payment. This work will be paid for at the contract unit price per TON for the screening, segregating and loading of the STOCKPILED AGGREGATE. No additional payment shall be made for the testing